

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Topeka, KS 67202

PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 119-201150001

LEASE NAME Wendell

WELL NUMBER 1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 10 TWP. 34S RGE. 30 or (W)

COUNTY Meade

Date Well Completed 9-21-95

Plugging Commenced 5-5-98

Plugging Completed 5-7-98

RECEIVED
KANSAS CORP. COMM.
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.
1998 JUL 13

LEASE OPERATOR Marlin Oil Corporation 7-13-1998

ADDRESS P. O. Box 14630, Oklahoma City, OK 73113-0630

PHONE#(405) 478-1900 OPERATORS LICENSE NO. 9228

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 5, 1998 (date)

by Lacy @ Dodge City office (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation U. Morrow Depth to Top 5860 Bottom 5888 T.D. 6200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	Oil & Gas	6022	6032			
L. Morrow	Water	5920	5926	8 5/8	1524	0
U. Morrow	Oil & Water	5860	5888	4 1/2	6120	3025

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Rigged up on 4 1/2 pump 20 sks of cement & 2 sks hulls to 5600-5888
Pump 50 sks @ 1550-1350. Pumped 40 sks of cement from 630-470'.
Capped well with 10 sks of cement from 40-0. Cut off & capped weld on steel ID plate. RD MO.

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address P. O. Box 506, 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Marlin Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

W. R. Lynn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 14630, OKC, OK 73113-0630

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 98

[Signature]
Notary Public

My Commission Expires: June 30, 2002

USE ONLY ONE SIDE OF EACH FORM