

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20472 - 0000

LEASE NAME Adams

WELL NUMBER 1-30

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1980 Ft. from (S/N) Line of Section (circle one)

1980 Ft. from (E/W) Line of Section (circle one)

LEASE OPERATOR Merex Resources, Inc.

SPOT LOCATION CNW - SE

ADDRESS P.O. Box 50955

SEC. 30 TWP. 34 S. RGE 29W (E) or (W)

CITY, STATE, ZIP Amarillo, TX 79159

COUNTY Meade

PHONE#(806) 374-2369 OPERATORS LICENSE NO. 31581

Date Well Completed 1-30-95

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 7-6-95

Date Plugging Completed 7-7-95

The plugging proposal was approved on July 6, 1995 (date)

by Glen Barlow (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation(s) Council Grove Depth to Top 2980 Bottom 3494 T.D. 3730PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Anhydrite	none			8 5/8	1543	none
Morrow	Gas	5815	5880	4 1/2	6045	2525
Council Grove	Gas	2980	3275	4 1/2	6045	2525

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @ 2930' with 2 sx cement. Pump 43 BBL mud down casing load hole.
Shot 4 1/2 casing off @ 2525' and laydown. Pump 50 sx cement from 1565' to
1390', pump 40 sx plug from 550' to 418' and pump 10 sx plug from 30' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor H & K Plugging & Salvage

License No. 31705

Address P.O. Box 2742, Highway 152 West, Pampa, TX 79066

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Merex Resources, Inc.


STATE OF Texas COUNTY OF Potter, ss.

Ed Podzemny (Employee of Operator or (Operator) of above-described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ed Podzemny

(Address) P.O. Box 50955 Amarillo, TX 79159

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 95



Lynda B. Banger
Notary Public

NOV 17 1995
11-17-1995
RECEIVED
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS