

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

MAY 04 1984
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Clark SEC. 19 TWP 34S RGE. 24 W
Location as in quarters or footage from lines:
330' FSL & 330' FWL c/SW SW

		19	

Lease Owner IREX Corp
Lease Name KLINGER Well No. 1
Office Address 1331 17th Street, Suite 800, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 11-17-81
Application for plugging filed 4-17-84
Plugging commenced 4-18-84
Plugging completed 5-1-84
Reason for abandonment of well or producing formation uneconomical

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey

Producing formation Chester Depth to top 5615' bottom 5845' T.D. 6250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surf. Sd.	0'	636'	8-5/8"	635'	none
	Red Bed	636'	2045'	4-1/2"	6230'	4500'
	LM & SH	2045'	6250'			
	LM & SH	6250'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Started pulling pipe, pmpd 20 BM dn hole, Pmpd 1st plug @ 685'-585' w/50sxs class H cmt., 2nd plug @ 320'-220' w/40 sxs Class H cmt., Pmpd last plug @ 40' - 0' w/10 sxs class H cmt., cut-off & cap well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reeves & Wilson, Inc.

STATE OF Colorado COUNTY OF Denver, ss.
William H. Bayliff (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) William H. Bayliff
Same as Above Listing
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1984.

My Commission expires: 8.10.85

Deborah M. Olson
Deborah M. Olson Notary Public
1331-17th Street, Suite 800
Denver, CO 80202