

15-119-10254-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. W. Lange

Complete Address: Box 1034 Garden City, Kansas

Lease Name Adams Well No. # 1

Location C SW NE Sec. 24 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply Inc.

Address: Great Bend, Kansas License No. #5747

Operation Completed: Hour 2 PM Day 28 Month 9 Year 65

The Above well was plugged as follows:

13 3/8"-582' Circulated w/cement. 9 5/8"-2885' Cemented. 7"-6304'-Cemented.

4 1/2"-6200' Cemented. Plug back to 5912'. Plug bottom w/20 Sax. cement top cement at 5500'.

Mud 5500' to 600' Spotted 100 Sax. cement 600' to 500'.

Mud 500' to 35' Plug, 35 Sax. cement 35' to 0. Company Pump.

Pulled 5164' 4 1/2" pipe. Pulled 2760' 7" pipe. Pulled 342' 9 5/8" pipe.

I hereby certify that the above well was plugged as herein stated.

DATE 9/30/65

INV. NO. 1898-W

Signed: [Signature]
Well Plugging Supervisor