

Jc
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1966
4-22-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil & Gas Corporation

Complete Address: P.O.Box 158, Liberal, Kansas

Lease Name Dreyer Well No. 1-3

Location CSW Sec. 3 Twp. 32 Rge. 43 (EX) (W)

County Morton Total Depth 3405'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 20 Month 4 Year 1966

The Above well was plugged as follows:

8 5/8" to 616' Cirulated w/ cement. 5 1/2" to 3358' cemented.

Top Perforations 3144' Plug bottom w/ 20 sacks cement

Top of cement 3000' Mud 3000' to 650'

Spotted 35 sacks cement 650' to 550' Mud 550' to 45'

Plug, Hulls & 15 sacks 45' to 0'

Company Pump. Pulled 1900' of 5 1/2" casing.

~~Welded~~ Welded Plate on 8 5/8" Casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/23/66
INV. NO. 3086-4

Signed: Edgar J. Eves
Well Plugging Supervisor