

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
JAN 31 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Champlin Petroleum Company 1-31-1967

Complete Address: Box 552, Enid, Oklahoma

Lease Name Harrison Well No. 1-12

Location C NW Sec. 12 Twp. 32 Rge. 42 ~~(E)~~ (W)

County Morton Total Depth 5210'

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A   
~~Lost Hole X~~

Other well as hereafter indicated: None

Plugging Contractor: Dowell

Address: Box 1067, Guymon, Oklahoma License No. \_\_\_\_\_

Operation Completed: Hour 4:30PM Day 28 Month 1 Year 1966

The Above well was plugged as follows:

8 5/8" to 1447' circulated w/ cement. 2 7/8" to 5075' cemented.

Top perforations 5002' Perforations squeezed w/ 175 sacks cement.

Top of cement 4500' Mud 4500' to 1995'

Spotted 25 sacks cement 1995' to 1920' Mud 1920' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug hulls & 15 sacks cement 45' to 0' Dowell Pump Truck.

Backed out and pulled 1995' of 2 7/8" casing.

Lost 3013' of 1 1/4" tubing in hole and was left.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves  
Well Plugging Supervisor

INVOICED  
DATE 1/31/67  
INV. NO. 4693-W