

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

1-11-1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walters of Colorado Oil & Gas Corp. has this date requested permission to plug the following described well:

Mr. Walters guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil & Gas Corp.

Complete Address: Box 158 Liberal, Kansas

Lease Name: Dryer Well No. B-3

Location: SE SE NW Sec. 8 Twp. 32 Rge. 43 (E) (W)

County Morton Total Depth 3420' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Walters was instructed to plug the well as follows:

8 5/8"-612' Circulated w/cement, 5 1/2"-3396' Cemented. Top Perforations-3143'

Plug bottom w/20 Sax.cement top cement, 3000'. Mud 3000' to 650'

Spotted 35 Sax.cement 650' to 550' Mud 550' to 45'

Plug, 15 sax.cement 45' to 0

Very truly yours,

Conservation Division Agent