



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION
 Wichita, Kansas

12-27-1965

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Chase of Edwin Cox-Stone-Kirby has this

date requested permission to plug the following described well:

Mr. Chase guarantees payment of the plugging fee.

Operator's full Name: Edwin Cox Stone Kirby

Complete Address: Box 578, Kanheadton, Okla.

Lease Name: E. Wilson Well No. # 1

Location: C SE NW SE Sec. 10 Twp. 32S Rge. 43 (E)(W)

County Morton Total Depth 5383' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Chase was instructed to plug the well as follows:

8 5/8" - 1416' Circulated w/cement.

Mud 5383' to 3550' Spotted 100 Sax.cement 3550' to 2900'

Mud 2900' to 1400' Spotted 35 Sax.cement 1400' to 1300'

Mud 1300' to 45' Plug, Hulls. 15 Sax.cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent