

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Colo. Oil Co. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Company.

Complete Address: 915 Union Nalt. Bldg., Wichita, Kansas

Lease Name: Sauders Well No. 1

Location: SE SE NW Sec. 11 Twp. 32 Rge. 43 (W)

County: Morton Total Depth 5190' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 2134' circulated w/ cement. 5 1/2" to 5166' cemented.

Top perforations 2745' Plug bottom w/ 20 sacks cement.

Top of cement 2700' Mud 2700' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Lewis
Conservation Division Agent