

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

11-16-1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Walters of Colorado Oil & Gas Corp. has this

date requested permission to plug the following described well:

Mr. Walters guarantees payment of the plugging fee.Operator's full Name: Colorado Oil & Gas Corp.Complete Address: Box 158 Liberal, KansasLease Name: Saunders Well No. # 1-18Location: SW SW NE Sec. 18 Twp. 32 Rge. 43 (E) (W)County Morton Total Depth 3387 Oil WellGas Well  Input Well  SWD Well  D & A  Lost Hole Mr. Walters was instructed to plug the well as follows:8 5/8"-600' Circulated w/cement. 5 1/2"-3380' Cemented.Plug back to 3248' Perforations 3131' to 3143'Plug bottom w/20 Sax. cement top cement 3050' Mud 3050' to 650'M5 Sax. cement 650' to 550' Mud 550' to 45'Plug, 15 Sax. cement 45' to 0

Very truly yours,

  
Conservation Division Agent