

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Townsend of Cotton Pet. has this

date requested permission to plug the following described well:

Mr. Townsend guarantees payment of the plugging fee.

Operator's full Name: Cotton Petroleum Co.

Complete Address: 2121 S. Columbia, Tulsa, Oklahoma

Lease Name: Adams "C" Well No. 1

Location: 330' FNL & 330' FWL SE Sec. 24 Twp. 34 Rge. 30 (E)(W)

County: Meade Total Depth 3750' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Townsend was instructed to plug the well as follows:

8 5/8" to 662' circulated w/ cement. 4 1/2" to 3750' cemented.


Top perforations 3048' Plug bottom w/ 20 sacks cement.

Top of cement 2650' Mud 2650' to 650'

Spot 35 sacks cement 650' to 550' Mud 550' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent