



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Lange of R.W. Lange has this

date requested permission to plug the following described well:

Mr. Lange guarantees payment of the plugging fee.

Operator's full Name: R.W. Lange

Complete Address: Box 1034 Garden City, Kansas

Lease Name: Adams Well No. # 1

Location: C SW NE Sec. 24 Twp. 34 Rge. 30 (E/W)

County Meade Total Depth 6510' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lange was instructed to plug the well as follows:


13 3/8"-582' Circulated w/cement. 9 5/8"-2885' Cemented. 7"-6304' Cemented.

4 1/2"-6200' Cemented. Plug back to 5912'. Plug bottom w/20 Sax. cement top
Cement at 5500'.

Mud 5500' to 600' Spotted 100 Sax. cement 600' to 500'

Mud 500' to 35' Plug, 35 Sax. cement 35' to 0

Very truly yours,


Conservation Division Agent