

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 31 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Reimert of Champlin Petro. Co. has this  
date requested permission to plug the following described well:

Mr. Reimert guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Company

Complete Address: Box 552, Enid, Oklahoma

Lease Name: Harrison Well No. 1-12

Location: C NW Sec. 12 Twp. 32 Rge. 42 ~~(E)~~ (W)

County Morton Total Depth 5210' Oil Well     

Gas Well ~~X~~ Input Well      SWD Well      D & A X Lost Hole ~~X~~

Mr. Reimert was instructed to plug the well as follows:

8 5/8" to 1447' circulated w/ cement . 2 7/8" to 5075' cemented.

Top perforations 5002' Perforations squeezed w/ 175 sacks cement.

Top of cement 4500' Mud 4500' to 1995'

Spotted 25sacks cement 1995' to 1920' Mud 1920' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edna A. Eves  
Conservation Division Agent