

R

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Smith "G" Well No. 1

Location C NW 1/4 Sec. 15 Twp. 32 Rge. 38 (W)

County Stevens Total Depth 2892'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: None

Plugging Contractor: Service Drilling Co.

Address: Tulsa, Okla. License No. \_\_\_\_\_

Operation Completed: Hour 8:30PM Day 23 Month 5 Year 1966

The Above well was plugged as follows:

8 5/8" to 609 circulated w/ cement. T.D. 2892'

Lost four drill collars & some drill Pipe on bottom & hole was abandoned.

Mud 2892' to 660' Spotted 35 sacks of cement 660' to 545'

Mud 545' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Welded Plate on 8 5/8" Haliburton Pump Truck.

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

MAY 26 1966

DATE 5-26-66

CONSERVATION DIVISION  
Wichita, Kansas

Signed: Edgar J. Eves  
Well Plugging Supervisor

INV. NO. 3281-W