

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name Howell Well No. # B-1

Location C NW NE Sec. 20 Twp. 32 Rge. 38 (E) (W)

County Stevens Total Depth 3100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Burriss

Address: Garden City, Kansas License No. 359

Operation Completed: Hour 330 PM Day 17 Month 12 Year 65

The Above well was plugged as follows:

8 5/8"-611' Circulated w/cement. 4 1/2"-3100' Cemented. Top perforations-2902'

2 7/8" tubing w/packer-2880'. Plug bottom w/140 Sax. cement top cement. 2530'

Mud 2530' to 625'. Spotted 40 Sax. cement 625' to 500'.

Mud 500' to 40' Plug, 15 Sax. cement 40' to 0

Left 430' tubing and packer in hole. Pulled 877' 4 1/2" pipe.

Pulled 2450' 2 7/8" tubing. Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/21/65
INV. NO. 2454-W

Signed: [Signature]
Well Plugging Supervisor