

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO: J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Location: Approx C NE NW

County: Stevens Sec. 36 Twp. 32 Rge. 37 W (~~W~~) (W)

Name of Field or Pool: Wildcat (Hugoton) Total Depth: 6331'

I have this date completed supervision of plugging of:

Well No. 1-36 Lease Lightcap Area 17

Operator's Full Name Shell Oil Company

Complete Address: P. O. Box 7111 Great Bend, Kansas

Plugging Contractor: Co. Rig No. 18

Address: _____ License No. _____

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour _____ Day 28 Month November Year 1959

The above well was plugged as follows:

Hole full of heavy rotary mud. Pumped in 150 sax cement by Halliburton, leaving plug 2900-2420. Pushed 8-5/8" Halliburton plug to 567. Capped plug w/20 sax cement to 505. Pushed 8-5/8" Halliburton plug to 31. Capped plug w/10 sax cement to top.

<u>6331-2900 PB w/mud</u>	<u>567- 505 PB w/cement</u>
<u>2900-2420 PB w/cement</u>	<u>505- 31 PB w/mud</u>
<u>2420-567 PB w/mud</u>	<u>31- 0 PB w/cement</u>

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: S. S. Guider signed
Well Plugging Supervisor
for Frank Broadfoot 6-19-62

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Well Plugging Supervisor

Reviewed: _____
Field Supervisor

Remarks:

INVOICED

DATE 6/19/62

INV. NO. 5206-w