

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-64  
NOV 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil & Gas Corp.

Complete Address: Box 158 Liberal, Kansas

Lease Name Dryer Well No. # 1-7

Location SW SW NE Sec. 7 Twp. 32 Rge. 43 (BY) (W)

County Morton Total Depth 3405'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 3 PM Day 12 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" - 622' Circulated w/cement. 5 1/2" - 3410' Cemented.

Plug back to 3158' Perforations 3144' to 3153'

Plug bottom w/20 Sax. cement to cement 3050' Mud 3050' to 650'

Spotted 35 Sax. cement 650' to 550' Mud 550' to 45'

Plug 15 Sax. cement 45' to 0 Company Pump. Pulled 2430' 5 1/2" pipe.

Cut surface off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

DATE 11/16/64

INV. NO. 163-W

Signed: [Signature]  
Well Plugging Supervisor