

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
JUL 6 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Morton

Location: C. SE SE Sec. 17 Twp. 32 Rge. 43 (E) (W)

Name of Field: _____ Total Depth: 4320

I have this date completed supervision of plugging of:

Lease Name: Huber-Dreyer Well No. 1

Operator's Full Name: Colorado Oil & Gas Corp.

Complete Address: P.O. Box 999 Liberal, Kans.

Plugging Contractor: Knight Casing Pulling Co.

Address: Great Bend, Kans License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 8pm Day 20 Month June Year 1960

The above well was plugged as follows:

PBTD 4001. Top perf 3993' 8 5/8" at 1461'
Hole was sealed to 3980 and 5 sacks cement dumped
with dump trailer. 5 1/2" pulled. Hole was mudded to
800'. Rock bridge set from 800' to 790'. Cement
dumped on bridge. Mud to 400'. Rock bridge set from 400'
to 390'. 20 sacks cement poured on bridge. Mud to 40'.
Rock bridge from 40' to 30'. 10 sacks cement poured to base
of cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 7-7-60
INV. NO. 1583-W