

15-129-10067-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil & Gas Corp.

Complete Address: Box 158 Liberal, Kansas

Lease Name Saunders Well No. # 1-18

Location SW SW NE Sec. 18 Twp. 32 Rge. 43 (BY) (W)

County Morton Total Depth 3387'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 14 Month 11 Year 64

The Above well was plugged as follows:

8 5/8"-600' Circulated w/cement. 5 1/2"-3380' Cemented.

Plug back to 3248' Perforations 3131' to 3143'

Plug bottom w/20' Sax. cement top cement 3050' Mud 3050' to 650'

35' Sax. cement 650' to 550' Mud 550' to 45'

Plug, 15' Sax. cement 45' to 0 Company Pump.

Pulled 1123' 5 1/2" pipe. Cut surface off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/16/64

INV. NO. 164-W

Signed: [Signature]  
Well Plugging Supervisor