

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 110-40
LOCATION C SE NW
SEC. 30 TWP. 34 RGE. 29W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-F Lease H. G. Adams Box 994
Operator Columbian Fuel Corporation Address Liberal, Kansas
Field _____ County Meade
Total Depth 6300 Feet.

(Describe briefly the manner in which the well was plugged)

- 5950' - 6300' Plugged w/ rotary mud - pumped
- 5850' - 5950' Plugged w/ cement - pumped
- 4850' - 5850' Plugged w/ rotary mud - pumped
- 4750' - 4850' Plugged w/ cement - pumped
- 2650' - 4750' Plugged w/ rotary mud - pumped
- 2550' - 2650' Plugged w/ cement - pumped
- 300 - 2550' Plugged w/ rotary mud - pumped
- 50 - 300' plugged w/ crushed rock - dumped
- 15' - 50' Plugged w/ cement (35 sk) dumped
- 10' - 15' Plugged w/ crushed rock - dumped
- 0-10' Plugged w/ cement (10sk) dumped

RECEIVED *DR Phillips*
STATE CORPORATION COMMISSION District Conservation Agent

OCT 30 1951 Date 10-22-51

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 30 134 R29W
BOOK PAGE 110 LINE 40