

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION ~~SE~~ NE NE

SEC. 12 TWP. 34 RGE. 27

60

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Isaac

Operator Alamo Corporation Address 1006 Lubbock Nat'l. Bank Bldg.

Field _____ County Meade Lubbock, Texas

Total Depth 6175 Feet.

Plugging Contractor Daco Lease and Well Service

Plugging Contractor's License No. _____

Address Borger Texas

(Describe Briefly the manner in which the well was plugged)

The hole was clean after abandonment with perms. 6004-12 open. 20 sacks of cement were pumped in with plugs behind. The plug was pumped to 5880'. 5 1/2" casing was then shot off at 5425' and pulled. 8 1/8" casing was then shot off at 1804' and pulled. Hole was then filled to 275' with heavy mud and plug was set at 275' with 20 sacks cement on top. Hole was then filled to 20' with heavy mud. A plug was set at 20' with a wire line, and hole was then filled to cellar with cement.

R. J. Phillippe
District Conservation Agent

RECEIVED
STATE CORPORATION COMMISSION

Date 7/1/57

JUL 11 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 12 T. 34 R. 27W
BOOK PAGE 27 LINE 35