

1031529

STATE CORPORATION COMMISSION

API NUMBER 15-129-21,594-0000

NE NE SEC. 21, T 32 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME RENSHAW WELL # 21-1

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON

205.40

OPERATOR LICENSE # 32154

WELL TOTAL DEPTH 6320 FEET

OPERATOR: SAGEBRUSH OPERATING LLC PRODUCTION CSG: SIZE        " FEET

NAME AND 1888 SHERMAN STREET, SUITE 500 SURFACE CASING: SIZE 8 5/8" @ 1708' WITH SX

ADDRESS DENVER, CO 80203

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A X

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 7:00 PM DAY: 24 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:       

1ST PLUG AT 2850' WITH 50 SX CEMENT. 2ND PLUG AT 1710' WITH 50 SX CEMENT.

3RD PLUG AT 660' WITH 25 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE

WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE X

OPERATIONS COMPLETED: HOUR: 11:00 PM DAY: 24 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2850' WITH 50 SX CEMENT. 2ND PLUG AT 1710' WITH 50 SX CEMENT.

3RD PLUG AT 660' WITH 25 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-99  
OCT 28 1999

REMARKS USED 60/90 POZMIX 6% GEL BY ALLIED.

CONSERVATION DIVISION  
Wichita Kansas

I DID NOT OBSERVE THIS PLUGGING. IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.

DATE 10-24-99

SIGNED Steve Durrant

(TECHNICIAN)

FORM CP-2/3

INV. NO. 60378

2