

1052403

TO: STATE CORPORATION COMMISSION

API NUMBER 15-189-22,322 <sup>-00-00</sup>  
E/2 SW NE SEC. 11, T 32 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 1976 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1469 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MLP SCHMIDT FARMS INC A WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 196.95

OPERATOR LICENSE # 5447

*6/23*

WELL TOTAL DEPTH 6060 FEET

OPERATOR: OXY USA, INC

PRODUCTION CSG: SIZE        " FEET

NAME AND BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 1720' WITH        SX

ADDRESS LIBERAL, KS 67905-2528

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A X

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR DUKE DRILLING CO., INC. LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410 WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 8:00 PM DAY: 23 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CAL WILEY

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:       

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1750' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

       PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE X

OPERATIONS COMPLETED: HOUR: 11:00 PM DAY: 23 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1750' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING. 7/5/00

**NOTICED**  
NO. 1060008

Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 03 2000  
CONSERVATION DIVISION  
Wichita, Kansas