

1052349
TO:

API NUMBER 15-189-22,320-00-00

STATE CORPORATION COMMISSION

C NE SW SEC. 11, T 32 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION

1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME YOUNGREN "M" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 206.38

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 6350' FEET

OPERATOR: ANADARKO PETROLEUM CORPORATION CONDUCTOR PIPE: SIZE _____ "FEET _____

NAME AND ADDRESS P. O. BOX 351 SURFACE CASING: SIZE 8 5/8" FEET 1690'

ADDRESS LIBERAL, KS 67905

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR NORSEMAN DRILLING, INC. LICENSE NUMBER 3779

ADDRESS 200 E FIRST ST STE 307, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 3:30 AM DAY: 22 MONTH: OCTOBER YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW

(COMPANY NAME) ANADARKO PETROLEUM CORPORATION (PHONE) 316-624-6253

WERE: TO FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH DRILL PIPE

1ST PLUG AT 3000' WITH 100 SX CEMENT, 2ND PLUG AT 1730' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT

CIRCULATE RAT HOLE WITH 15 SX OF CEMENT. CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:00AM DAY: 21 MONTH: OCTOBER YEAR: 1999

ACTUAL PLUGGING REPORT 1ST PLUG AT 3000' WITH 100 SX CEMENT,

2ND PLUG AT 1730' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 40 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT,

CIRCULATE RATHOLE WITH 15 SX OF CEMENT

CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 12/3

NOV 24 1999

NO. 60894

11-23-99

CONSERVATION DIVISION
Wichita Kansas

REMARKS: USED 60/40 POZMIX 6% GEL CEMENT PUMPED BY HALLIBURTON CEMENTING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey
(TECHNICIAN) FORM CP-2/3