

1031056

1-6

52 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-21,032-0000
C N/2 SE SE, SEC. 4, T. 32 S, R. 39 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

990 feet from S section line
660 feet from E section line

Operator: OXY USA Inc.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Israel B Well # 6
County Morton 195.00
Well Total Depth 6000 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1724

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Zenith Drilling Corporation License Number 5141
Address 505 4th Financial Center, Wichita, KS 67202

Company to plug at: Hour: 1:30 p.m. Day: 6 Month: 1 Year: 1990

Plugging proposal received from Tim Voss

(company name) OXY USA Inc. (phone) 405-749-2471

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Top 1714'
1st plug at 5630' with 100 sx cement, 2nd plug at 2750' with 140 sx cement,
3rd plug at 1730' with 50 sx cement, 4th plug at 810' with 40 sx cement,
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 p.m. Day: 6 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 5630' with 100 sx cement,
2nd plug at 2750' with 140 sx cement, 3rd plug at 1730' with 50 sx cement,
4th plug at 810' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel by Western. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 29 1990

INV. NO. 27223

FEB 28 1990

Signed Steve Durrant (TECHNICIAN)

FORM EFFECTIVE DATE: 12-23-89
FORM C-1 12/88

State of Kansas ¹⁵ 129-21,032-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date December 23, 1989
month day year

CN/2 SE/4 SE/4 Sec 4 Twp 32 S, Rg 39 East West

OPERATOR: License # 5447
Name: OXY USA, Inc.
Address: P. O. Box 26100
City/State/Zip: Oklahoma City, OK 73126-0100
Contact Person: Raymond Hui
Phone: (405) 749-2471

990 feet from South line of Section
660 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # License on No-1
Name: Unknown at this time
Zenith Rig

County: Morton
Lease Name: Israel B Well #: 6
Field Name: East Kinsler

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWMO Disposal Wildcat Cable
 Seismic; # of Holes

Is this a Prorated Field? Morrow yes no
Target Formation(s): 660
Nearest lease or unit boundary: est. 3210 feet MSL

If OWMO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Ground Surface Elevation: _____ feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: _____

Depth to bottom of fresh water: 450 340'
Depth to bottom of usable water: 600 440'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 1650'
Length of Conductor pipe required: 40'

* Prorated: EAST KINSLER - Morrow Set 1790' at 8:30 on 12-26-89
Exp. 6/18/90

Projected Total Depth: 6000'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations: well farm pond other


DWR Permit #: _____
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

460' Alt. I Req.

The undersigned hereby affirms that she/he/it is the owner of the well described herein.

PUSHER Tim Voss
TD 6000 FORMATION Morrow
SURFACE PIPE 8 7/8 @ 1724
ANHYDRITE 1714 1/4 ELEVATION _____
STARTING TIME & DATE 1:30 pm 1-6-89
COMPLETION TIME & DATE 7:30 pm 1-6-89
1st PLUG @ 5630 FT. W/ 100 SX
2nd PLUG @ 2150 FT. W/ 140 SX
3rd PLUG @ 1730 FT. W/ 50 SX
4th PLUG @ 810 FT. W/ 40 SX
RAT HOLE CIRCULATED W/ 15 1/2 SX
MOUSE HOLE CIRCULATED W/ 0 SX
WATER WELL PLUGGED W/ Disintegration Water
CEMENT COMPANY Western
TECHNICIAN SD
TYPE OF CEMENT 60/40 permen
w/ 20% gel

STATE OF KANSAS
JAN 9 1990
CONSERVATION DIVISION
Wichita, Kansas



- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.