

1 020772

6-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,353-0060

C NW SW, SEC. 3, T 32 S, R 39 W/4
1980 feet from S section line

4620 feet from E section line

Lease Name MLP Gillespie A Well / 1

County Stevens

Well Total Depth 6270 203.77 feet

Conductor Pipe: Size 20" feet 40

Surface Casing: Size 8 5/8" feet 1716

TECHNICIAN'S PLUGGING REPORT

Operator License / 5447

Operator: OXY USA INC.

Name & Address P.O. Box 26100

Oklahoma City, OK 73126-0100

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Co. License Number 5866

Address 713 S. Simpson, Ulysses, KS 67880

Company to plug at: Hour: 9 a.m. Day: 23 Month: 6 Year: 19 94

Plugging proposal received from Tom Patton

(company name) J.W. Gibson Co. (phone) 316-353-1002

vers: 5 1/2" at 6256' w/1430 sx cement, PBSD 6148', Perfs at 5810-50'

1st plug set CIBP at 5775' with 2 sx cement on top,

2nd plug pump 75 sx cement at 2900', 3rd plug at 2300-1800' with 30 sx cement,

4th plug at 900' with 30 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 p.m. Day: 23 Month: 6

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5750' with 2 sx cement on top with bailer

2nd plug pumped 75 sx cement at 2900',

3rd plug pumped 30 sx cement at 1800',

4th plug pumped 30 sx cement at 700',

5th plug pumped 10 sx cement at 60 to -4'. Heavy mud between all plugs.

Remarks: Used Class H cement by Gibson. No casing recovery.

INVOICED

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE JUL 07 1994

WIL. NO. 40779

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 01 1994
CONSERVATION DIVISION