

To: 1 100179
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-22,155-0001
NW NW NW, SEC. 2, T 32 S, R 39 W/E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Vanselous A Well # 6
County Stevens 202.48
Well Total Depth 6230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1699

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 4 Month: 12 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 6212' w/235 sx cement, PBDT 6090', Perfs at 5808-16, 6060-66, 6072-88', CIBP 6109'
1st plug pump 25 sx cement with 2 sx hulls from 5808-5608',
2nd plug at 1730' with 50 sx cement, 3rd plug at 650' with 40 sx cement,
4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 4 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug spotted 25 sx cement with 2 sx hulls from 5808-5608',
2nd plug spotted 50 sx cement at 1730',
3rd plug spotted 40 sx cement at 650',
4th plug spotted 10 sx cement from 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1997 12-10-1997
CONSULTATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent & Horton. Recovered 2133' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-15-97

Signed Gary Winters
(TECHNICIAN)

INV. NO. 49678
12-4