

100154

9-3

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Spud date 4/23/66

NW NW SE SE, SEC. 2, T 32 S, R 39 W

1250 feet from S section line

1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Vanselous A Well # 2

Operator: Anadarko Petroleum Corporation

County Stevens 95.23

Name & Address P.O. Box 351

Well Total Depth 2930 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well X Input Well SKD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 2 Month: 9 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

was: 5 1/2" at 2928' w/200 sx cement, PBSD 2922', Perfs at 2712-2820' (10 sets)

1st plug pump 2 sx hulls and 35 sx cement, displace to 2662',

2nd plug spot 25 sx cement at cut off,

3rd plug spot 25 sx cement from 647-547', 9-9-97

4th plug spot 20 sx cement from 54-4',

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10 a.m. Day: 3 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement, displaced to 2662-2462',

2nd plug pumped 40 sx cement and displaced from 1600-1500', 9-9-97

3rd plug pumped 50 sx cement and spotted at 650',

4th plug spotted 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent and Casing. Recovered 1601' of 5 1/2" casing.

Additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 9-9-97

Signed Gary Winters (TECHNICIAN)

INV. NO. 48958

9-3