

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22366-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 1-32S-39W
990 feet from S Section Line, 1500 feet from E Section Line
Lease/Unit Name: YOUNGGREN N Well Number: 1
County: STEVENS Total Vertical Depth: 1746 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATION
Address: 1701 NORTH KANSAS AVE PO BOX 351
LIBERAL, KS 67905

Conductor Pipe: Size 20 feet: 100
Surface Casing: Size feet:
Production: Size feet:
Liner: Size feet:

\$ 56.78

Well Type: LH UIC Docket No: Date/Time to Plug: 03/23/2001 9:00 AM
Plug Co. License No.: 3779 Plug Co. Name: NORSEMAN DRILLING, INC.
Proposal Rcvd. from: GENE GRAVES Company: NORSEMAN DRILLING, INC. Phone: (316) 265-9408

Proposed Plugging Method: RUN DRILL PIPE TO 620' SPOT 100 SX MID-CON II 3% CC. TAG PLUG. RESPOT IF NECESSARY. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 03/23/2001 6:30 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

LOST CIRCULATION AT 1387'. RUN DRILL PIPE @ 620' & PUMPED 580 SX MIDCON C CMT 3% CC 1/4# POLY FLAKE 1% FWCA - 13.5# & 200 SX PREMT CMT 2% CC 1/8# POLY FLAKE - 14.5#. PULLED PIPE - WAIT 3 HOURS. RUN DRILL PIPE IN & TAG CMT @ 240'. LAID DOWN 2 JTS @ 180' PUMPED 350 SX MIDCON "C". CEMENT CIRCULATED.

INVOICED
DATE 3-30-01
TRV. NO. 2001061548

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 2001
CONSERVATION DIVISION
Wichita, Kansas

3-30-2001

Remarks: VARIOUS CMT BLENDS BY HALLIBURTON.

Plugged through: DP

District: 01

Signed

[Signature]
(TECHNICIAN)

MAR 29 2001

Form CP-2/3