

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22372-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 1-32S-39W
922 feet from S Section Line, 1473 feet from E Section Line
Lease/Unit Name: YOUNGGREN N Well Number: 1A
County: STEVENS Total Vertical Depth: 1616 feet

Operator License No.: 4549 Conductor Pipe: Size 20 feet: 80
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 13.375 feet: 619
Address: 1701 NORTH KANSAS AVE PO BOX 351 Production: Size feet:
LIBERAL, KS 67905 Liner: Size feet:

852.52

Well Type: LH UIC Docket No: Date/Time to Plug: 05/12/2001 2:00 PM
Plug Co. License No.: 3779 Plug Co. Name: NORSEMAN DRILLING, INC.
Proposal Rcvd. from: GENE GRAVES Company: ANADARKO Phone: (316) 624-6253

Proposed Plugging Method: 1ST PLUG AT 1216' WITH 100 SX CMT. 2ND PLUG AT 630' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 05/12/2001 9:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 1236' WITH 2-8" DRILL COLLARS, 1-6" DRILL COLLAR, 1-12" BOAT ANCHOR. LOST CIRCULATION AT 1216'. 1ST PLUG RAN DRILL PIPE TO 1080' & PUMP 100 SX 60/40 POZMIX 6% GEL 2% CC. HOLE CIRCULATED WHILE PUMPING CMT. 2ND PLUG PULLED DRILL PIPE TO 619' & PUMP 100 SX 60/40 POZMIX 6% GEL 2% CC. WAIT ON CMT 5 HOURS. TAGGED PLUG AT 540'. 3RD PLUG PULLED DRILL PIPE TO 40' CIRCULATE CMT TO SURFACE WITH 25 SX CMT.

INVOICED

DATE 5-29-01
INV. NO. 2001061849

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 21 2001
5-21-2001
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON.

Plugged through: DP

District: 01

Signed Steve Durrant
(TECHNICIAN)

MAY 15 2001

MP