

To: 1 100006
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-21,476-0000

E/2 NE, SEC. 35, T 32 S, R 38 W/E

3902 feet from S section line

660 feet from E section line

Lease Name Mobil WRD #2 Well # 1-35

County Stevens

Well Total Depth 6490 210.93 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1768

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Operator: McCoy Petroleum Corporation

Name: 3017 N. Cypress

Address: Wichita, KS 67226-4003

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address: P.O. Box 466, Ulysses, KS

Company to plug at: Hour: 4 p.m. Day: 21 Month: 12 Year: 19 95

Plugging proposal received from Tim Hintergardt

(company name) J.W. Gibson Well Service (phone) 316-353-1002

Perfs: 5 1/2" at 6193' w/670 sx cement, 2nd stage 510 sx cement, PBSD 6155',

Perfs at 6043-59, 6062-16, 6012-17, 6020-25'

1st plug set CIBP at 5970' and dump 2 sx cement on top,

2nd plug at 1800' with 50 sx cement, 3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1995 12-27-1995

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 8 p.m. Day: 21 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5970' with 2 sx cement on top,

2nd plug shot at 1993' and pulled to 1800', set 40 sx plug,

3rd plug pulled to 700' and set a 40 sx plug,

4th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Gibson. Recovered 1993' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE JAN 09 1996
INV. NO. 44447

Signed Gary Winters
(TECHNICIAN)