

1020853

API NUMBER 15-189-21,791-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 S/2 SW, SEC. 33, T 32 S, R 38 W/E
330 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lessee Name Quigg A Well # 1-33

Operator: McCoy Petroleum Corporation

County Stevens 201.50

Name & Address 3017 N. Cypress

Well Total Depth 6200 feet

Wichita, KS 67226-4003

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1448

Abandoned Oil Well _____ Gas Well X Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service Co. License Number 5866

Address P.O. Box 237, Henderson, CO 80640-0237

Company to plug at: Hour: 8:30 a.m. Day: 11 Month: 4 Year: 1995

Plugging proposal received from Tom Patton

(company name) J.W. Gibson Well Service Co. (phone) 303-289-2966

were: 5 1/2" at 6199' w/200 sx cement, TOC at 5300', Perfs at 6082-88, CIBP at 6072',
6034-42'--open

DV at 3129' w/250 sx cement, TOC 1500'

1st plug set CIBP at 5950' with 2 sx cement on top, load hole with mud,

2nd plug shoot pipe at 1408' and spot 50 sx cement,

3rd plug pump 40 sx cement at 712', 4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 11 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5950' with 2 sx cement on top. Loaded hole w/mud.

2nd plug shot pipe at 1408' and spotted 50 sx cement,

3rd plug pumped 40 sx cement at 712';

4th plug pumped 10 sx cement at 40 to -4'.

4-14-95

Remarks: Used common cement by J.W. Gibson. Recovered 1408' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-26-95
OBSERVE THIS PLUGGING.

DATE 4-26-95
INV. NO. 42697

STATE CORPORATION COMMISSION
RECEIVED
APR 1 1995
SIGNED Glenn R. Barlow
(TECHNICIAN)
CONSERVATION DIVISION
WICHITA, KANSAS