

To: 1 020426  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-9-92 55  
API NUMBER 15-189-20,116-0000  
C SE, SEC. 29, T. 32 S, R 38 W W&X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address 2319 N. Kansas  
Liberal, KS 67901

1320 feet from S section line  
1320 feet from E section line  
Lease Name Gustason Well # 2  
County Stevens 98.80  
Well Total Depth 3040 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 600  
Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mobil Oil Corporation License Number 5208  
Address 2319 N. Kansas, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 9 Month: 1 Year: 1992

Plugging proposal received from Tommy Romero  
(company name) Mobil Oil Corporation 316-544-5530 (phone)

were: 5 1/2" at 3039' w/415 sx cement, PBTD 3012', Perfs at 2840-2988'  
1st plug set CIBP at 2820' with 2 sx cement on top,  
2nd plug run tubing to bottom, circulate mud to surface, pump 10 sx cement at 1700-1610',  
3rd plug pull tubing to 700', circulate cement to surface,  
4th plug pump cement down annulus.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 9 Month: 1 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2820' with 2 sx cement on top,  
2nd plug ran tubing to bottom, circulated mud to surface, pumped 10 sx cement at 1700-1610',  
3rd plug pulled tubing to 700', circulated cement to surface,  
4th plug pumped cement down 8 5/8" annulus, approx. 9 bbl, pressured to 600 psi.

RECEIVED  
KANSAS CORPORATION COMMISSION  
1-16-92  
JAN 16 1992

Remarks: Used 60/40 Pozmix by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this report.)  
Observe this plugging.

INVOICED

DATE JAN 29 1992  
INV. NO. 34413

Signed Glenn R. Barlow  
(TECHNICIAN)