

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-10010-00-01
Spot: CNWSE Sec/Twnshp/Rge: 16-32S-38W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: MCCLURE Well Number: 2-16
County: STEVENS Total Vertical Depth: 6085 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet: \$197.76
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 13 feet: 586 WITH 575 SX CMT
Address: 17001 NORTHCHASE DRIVE Production: Size 8.625 feet: 3047 WITH 850 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet: _____

Well Type: SWD UIC Docket No: D19627.0 Date/Time to Plug: 06/18/2002 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: RTIH TO 1650' PUMP 5 SX HULLS & 70 SX CMT. PTUT 1200'. LOAD WITH MUD. PTUT 600' & PUMP 40 SX CMT. PTUT 40' & PUMP 15 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/19/2002 11:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2760'. PERFS AT 1500-1600'. 06/18/02: RUN IN HOLE WITH TUBING, STACKED OUT AT 1270'. WELL SANDED IN 210' ABOVE PERFS. PULL OUT OF HOLE TUBING TO 1260'. PUMP 50 SX CMT INSIDE 8 5/8". SDON. 06/19/02: 1ST PLUG RUN IN HOLE WITH TUBING, TAG BOTTOM PLUG AT 1170'. CIRCULATE HOLE WITH MUD. 2ND PLUG PULL OUT OF HOLE TO 600' & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40', LOAD HOLE WITH MUD AND PUMP 10 SX CMT TO SURFACE. PUMP 10 SX CMT DOWN ANNULUS. PRESSURE TO 500 PSIG & SHUT IN.

RECEIVED

SEP 03 2002

9-3-2002

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Jim Holland PERTHE
(TECHNICIAN)

INVOICE AUG 14 2002

DATE

9-4-02

INV. NO.

2003060470