

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-10005-00-00
Spot: CNE Sec/Twnshp/Rge: 18-32S-38W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: ROACH A Well Number: 1
County: STEVENS Total Vertical Depth: 3035 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA, I
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

Conductor Pipe: Size feet: 898.64
Surface Casing: Size 8.625 feet: 612 WITH 400 SX CMT
Production: Size 5.5 feet: 3033 WITH 200 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/06/2002 3:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2775'. PLUG AT 620' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/07/2002 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 2955'. PERFS AT 2836-2920'. TOC @ 2200'. CASING LEAK AT 1395-1418'. SET CIBP @ 2775' WITH 10 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG CUT CASING OFF AT 1400'. PULL 1 JOINT & PUMP 40 SX CMT. DIDN'T CIRCULATE. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TP 650'. LOAD HOLE WITH MUD. SDON. 11/07/02: PUMP 40 SX CMT AT 650'. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE WITH MUD & PUMP 10 SX CMT TO SURFACE.

RECEIVED
NOV 20 2002
KCC WICHITA
11-20-2002

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1428' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Jim Holland PERTH
(TECHNICIAN)

INVOICED
DATE 11-21-02
INV. NO. 2003060847

Form CP 2/3