

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-30085-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 20-32S-38W
660 feet from N Section Line, 2080 feet from E Section Line
Lease/Unit Name: HOWELL B Well Number: 2
County: STEVENS Total Vertical Depth: 3030 feet

Operator License No.: 4824 Conductor Pipe: Size _____ feet:
Op Name: PIONEER NATURAL RESOURCES USA, L Surface Casing: Size 8.625 feet: 594 WITH 400 SX CMT \$98.48
Address: 5205 N. O'CONNOR BLVD. Production: Size 5.5 feet: 3030 WITH 200 SX CMT
IRVING, TX 75039 Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/06/2001 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2800' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/06/2001 5:30 PM KCC Agent: HILTON HIXON

Actual Plugging Report:

PBTD 2992'. PERFS AT 2836-2988'. SET CIBP @ 2800' WITH 2 SX CMT. 1ST PLUG AT 890' WITH 40 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 03-07-2001
INV. NO. 2001061430

RECEIVED
STATE CORPORATION COMMISSION

FEB - 8 2001
2-8-2001

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 900' OF 5 1/2" CASING. CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed _____

J. F. Steffen
(TECHNICIAN)

FEB 07 2001

Form CP-2