

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22450-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 21-32S-38W
2310 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: HJV DUDLEY A Well Number: 1
County: STEVENS Total Vertical Depth: 6415 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6408 WITH 145 SX CMT
Surface Casing Size: 8.625 feet: 1775 WITH 535 SX CMT
\$208.49

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/27/2003 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# UHLLS & 20 SX CMT. 50 SX CMT FROM 1825-1677'. 40 SX CMT FROM 600-476'. 10 SX CMT FROM 40-0'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/27/2003 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6347'. PERFS AT 6061-69'. CIBP @ 6280'. PERFS AT 6294-6301'. PUMP 200# HULLS WITH 20 SX CMT. DISPLACE TO BOTTOM WITH MUD. PRESSURE TO 500 SPIG & SHUT IN. PULL STRETCH. SHOOT AT 5000'. PIPE STUCK. SHOOT AT 4300'. PIPE STUCK. SHOOT AT 3484'. 1ST PLUG PULL OUT OF HOLE TO 1830'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 31 2003
KCC WICHITA
10-31-2003

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 3484' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 10-31-03
INV. NO. 200406071

Form 6130