

To: 1 070906  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-16 API NUMBER 15- 189-21,464-0000 182 R

App. C W/2, SEC. 1, T 32 S, R 37 W/E  
2540 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address 2319 North Kansas  
Liberal, KS 67901

Lease Name Brower Unit Well # 3  
County Stevens 209.62  
Well Total Depth 6450 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1820

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Unit Drilling & Exploration Co. License Number 9137  
Address P.O. Box 702500, Tulsa, OK 74136

Company to plug at: Hour: \_\_\_\_\_ Day: 15 Month: 1 Year: 19 91

Plugging proposal received from Jay Cunningham  
(company name) Unit Drilling & Exploration Co. (phone) 918-493-7700

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3120'  
1st plug at Base of Hugoton/Council Grove with 100 sx cement,  
2nd plug at 1850' with 50 sx cement, 3rd plug at 900' with 40 sx cement,  
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: \_\_\_\_\_ Day: 16 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3260-2695' with 100 sx cement,  
2nd plug at 1840-1651' with 50 sx cement,  
3rd plug at 920-715' with 50 sx cement, 4th plug at 430-260' with 40 sx cement,  
5th plug at 40-0' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1991  
CONSERVATION DIVISION  
Wichita, Kansas.

Remarks: Used 60/40 Pozmix 6% gel by C & C Mud.  
(If additional description is necessary, use BACK of this form.) 1-25-1991

INVOICED  
(If back of form) observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN) SDW

DATE FEB 12 1991  
INV. NO. 30703