

15-189-10177-0001

To: 100010
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-189-00144 NA
C SE _____, SEC. 17, T 32 S, R 37
1320 feet from S section line
1320 feet from E section line

1-9

TECHNICIAN'S PLUGGING REPORT
Operator License # 5208
Operator: Mobil Oil Corp.
Name: _____
Address: P.O. Box 2173
Liberal, KS 67905-2173

Lease Name Moorhead Unit Well # 1
County Stevens
Well Total Depth 2850 92.63 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 12 1/2 feet 611

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Patrick Well Service Inc. License Number _____

Address: P.O. Box 1273, Liberal, KS 67905-1273

Company to plug at: Hour: 10 a.m. Day: 8 Month: 1 Year: 19 96

Plugging proposal received from Tom Romero

(company name) Mobil Oil Corp. (phone) 316-544-5547

logs: 9" at 2405' w/75 sx cement, 7" liner at 2368-2612', 5 1/2" liner at 2612-2806' cemented (not
PRTD 2806', Perfs at 2593-2785' 1st plug kill well, pump 50 bbls. mud and 50 sx cement,
2nd plug at 1740' with 50 sx cement,
3rd plug at 660', circulate cement to surface.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None 1-17-1996

Operations Completed: Hour: 1:30 p.m. Day: 9 Month: _____

RECEIVED 19 96
STATE CORPORATION COMMISSION

ACTUAL PLUGGING REPORT Set with 50 sx Thix/Tropic (FRS) and 500 lbs. hulls. Let set.

JAN 17 1996

Ran tubing and tagged plug. 2nd plug mixed additional 50 sx cement with 300 lbs. hulls and

CONSERVATION DIVISION

spotted on top of 1st plug, 3rd plug pulled tubing to 1752', circulated hole and set a 50

sx plug, 4th plug pulled tubing, perforated at 662', circulated hole with 9# gel, pumped

415 sx cement; cement circulated. Cement at top inside and out.

Remarks: Used 60/40 Pozmix by Dowell. No casing recovery.
(Additional description is necessary, use BACK of this form.)

INVOICED

DATE: JAN 23 1996
I (did / ~~did not~~) observe this plugging.

Signed: Gary Wilshire (TECHNICIAN)

INV. NO. 44691