

1100258

TO STATE CORPORATION COMMISSION

10-30

API NUMBER 15-189-20,200-0000
C NW SEC. 19, T 32 S, R 37 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CHARITY "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 97.73

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 3007 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 5 1/2" @ 3007' WITH 650 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 596' WITH 450 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 29 MONTH: 10 YEAR: 1998
HOUR: 1:00 PM DAY: 30 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING INC (PHONE) 405-854-6515

WERE: PERFS AT 2895-2994

1ST PLUG SPOT 25SX CEMENT & 400# HULLS FROM 2895' TO 2650'. GEL SPACER TO 1750'. 2ND
PLUG SPOT 25 SX CEMENT PLUG FROM 1750-1550. 3RD PLUG SPOT 70 SX CEMENT FROM 700' TO SUR-
FACE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 29 MONTH: 10 YEAR: 1998
HOUR: 2:00 PM DAY: 30 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG ON 10-28-98 SPOT 25 SX CEMENT & 400# HULLS FROM 2895'-2650'. GEL SPACER TO 1750'.
2ND PLUG SPOT 25 SX CEMENT PLUG FROM 1750' -1550'. 3RD PLUG SPOT 70 SX CEMENT PLUG FROM
700' TO SURFACE. CEMENT FELL TO 580' BELOW SURFACE. ON 10-30-98 TAG CEMENT @ 580'.
4TH PLUG FILL PIPE TO SURFACE WITH 60 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

11-5-99

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

11-6-98
60270