

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-10051-00-00  
Spot: CNW Sec/Twnshp/Rge: 14-32S-42W  
1320 feet from N Section Line, 3960 feet from E Section Line  
Lease/Unit Name: JACKSON Well Number: 1-14  
County: MORTON Total Vertical Depth: 3375 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN, LLC  
Address: 3200 FIRST PLACE TOWER  
TULSA, OK 74103

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 626 WITH 400 SX CMT  
Production: Size 5.5 feet: 3290 WITH 375 SX CMT  
Liner: Size \_\_\_\_\_ feet: 109.69

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2000 12:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: DUMP 2 SX CMT ON TOP OF SAND PLUG @ 2700'. CUT 5-1/2" CSG. @ 1500' & PULL CSG. SPOT A 50' CMT PLUG @ CUTOFF POINT, 100' PLUG ACROSS CSG. SHOE, 40' TO SURFACE. CUT OFF CSG. 3' BELOW GL & WELD ON I.D. PLATE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/20/2000 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2808-3168'. TOP CMT AT 1630'. SANDED BACK TO 2572' WITH SAND AND 2 SX CMT ON TOP. CASING LEAK APPROXIMATELY 1100'. PUMPED DOWN 5 1/2" 200# HULLS & 25 SX CMT. DISPLACED WITH 21 BBL MUD TO 900'. HAD 100# PRESSURE BLEED OFF AND CASING STAYED LOADED. SHOT CASING AT 660'. PULLED TO 655'. LOADED HOLE WITH 25 BBL MUD CIRCULATING TO SURFACE. PUMPED 50 SX CMT DISPLACED WITH 11 BBL MUD. PULLED CASING TO 40' & PUMPED 10 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 02 2001  
CONSERVATION DIVISION  
WICHITA KS

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 660' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Kevin D Strube  
(TECHNICIAN)

INVOICED

DATE 1/3/01

DEC 22 2000

WWW.FORD 2001061225

MP