

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10074-00-00
Spot: CNW Sec/Twnshp/Rge: 18-32S-42W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: STOOPS Well Number: 1-18
County: MORTON Total Vertical Depth: 3330 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 634 WITH 425 SX CMT
Production: Size 5.5 feet: 3230 WITH 300 SX CMT
Liner: Size _____ feet: 108.23

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/14/2000 3:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG PUMP 25 SX CMT & 200# HULLS. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/14/2000 6:30 PM KCC Agent: HILTON HIXON

Actual Plugging Report:
PERFS AT 3100-3115'. SET CIBP @ 2700' & 2 SX CMT ON TOP. 1ST PLUG AT 803' WITH 25 SX CMT. 2ND PLUG AT 654' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 803' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed J.F. Sifon
(TECHNICIAN)

INVOICED
DATE 12/20/00
INV. NO. 2001064155

DEC 15 2000

MP

Form CP 103