

To: 1 100058
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-129-00006-0000
API NUMBER 15- Drilled 1/55
C NW, SEC. 22, T 32 S, R 42 W/EX

7-15
TECHNICIAN'S PLUGGING REPORT

Operator License / 6593
Operator: Coastal Oil & Gas Corporation
Name & Address: 9 Greenway Plaza, Ste. 2751
Houston, TX 77046

3960 feet from S section line
3960 feet from E section line
Lease Name Bender Well / 1-22
County Morton 138.38
Well Total Depth 4258 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 641

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dowell License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 15 Month: 7 Year: 19 96

Plugging proposal received from Don

(company name) Dowell (phone) _____

was: 5 1/2" at 4251' w/500 sx cement, PBSD 3270', Perfs at 2787-3264' Casing Leak @ 1029'

1st plug set CIBP at 2930', mud to 1000',

2nd plug set CIBP at 1000', mud to 600',

3rd plug perforate casing at 670', circulate cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 22 1996
7-22-96
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 15 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2930', filled to 1000' with mud,

2nd plug set CIBP at 1000', filled to 600' with mud,

3rd plug perforated at 670', circulated cement to surface with 175 sx.

Pressured to 200 psi on backside.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 7-24-96

Signed Gary Winters
(TECHNICIAN)

INV. NO. 46083

7-15 SEP 27 1996 NOV 04 1996