

1100208

TO: 3-5 API NUMBER 15 - 129-20797-0000

STATE CORPORATION COMMISSION C SW NE, SEC. 28 T 32 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 1980' FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980' FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME PANKRATZ WELL # 1-28

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON 176.48

OPERATOR LICENSE # 3871 WELL TOTAL DEPTH 5430 FEET

OPERATOR: HUGOTON ENERGY CORPORATION ^{Surface} PRODUCTION CSG: SIZE 8 5/8" FEET 1621'

NAME AND 301 N. MAIN ST. SUITE 1900 ^{Production} SURFACE CASING: SIZE 5 1/2" FEET 5430' w/ 350 sy

ADDRESS WICHITA, KANSAS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING LICENSE NUMBER 31529

ADDRESS P.O. BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 5 MONTH: 3 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING (PHONE) (316) 938-2943

WERE: PBTD 5400', PERFS 4916-4926,

1ST PLUG SAND BACK TO 4830' AND DUMP 5 SX CEMENT ON TOP OF SAND WITH BAILER

2ND PLUG PUMP 3 SX HULLS, 10 SX GEL, 50 SX CEMENT, 15 SX GEL, 175 SX CEMENT 3-13-98

 PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 DAY: 5 MONTH: 3 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG SAND BACK TO 4830' AND DUMP 5 SX CEMENT ON TOP OF SAND

WITH BAILER.

2ND PLUG PUMP 3 SX HULLS, 10 SX GEL, 50 SX CEMENT, 15 SX GEL, 175 SX CEMENT

PUMPING PRESSURE 0-700 PSI - SHUT IN PRESSURE 150 PSI

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED, RECOVERED 2800' 5 1/2"
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Jay McIntire
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 3-20-98

INV. NO. 50282

RECEIVED
KANSAS CORP COM
1998 MAR 13