

To: 1 070362
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-19-87
API NUMBER 15- 129-20,867-0000

C S/2 NE SW, SEC. 29, T 32 S, R 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6378

Operator: Hawkins Oil & Gas, Inc.
Name & Address: Box 1282
Liberal, KS 67901

1650 feet from S section line

3300 feet from E section line

Lease Name Smith Well # 1-29

County Morton 175.50

Well Total Depth 5400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1411

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 19 Month: 6 Year: 19 87

Plugging proposal received from Tom Heskett

(company name) Murfin Drilling Company (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1399'

1st plug at 3600' with 40 sx cement, 2nd plug at 2850' with 40 sx cement,

3rd plug at 1440' with 50 sx cement, 4th plug at 1000' with 20 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:15 a.m. Day: 19 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3600' with 40 sx cement,

2nd plug at 2850' with 40 sx cement,

3rd plug at 1440' with 50 sx cement,

4th plug at 1000' with 20 sx cement, 5th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.
(if additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 6-25-87

INV. NO. 17352

Signed Dan Goodrow (TECHNICIAN)

JUN 24 1987
06-24-87
CONSERVATION DIVISION
Wichita, Kansas
6-24-87

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 18 1987
month day year

API Number 15-129-29867-0000

OPERATOR: License # 6378
Name Hawkins Oil & Gas, Inc.
Address Box 1282
City/State/Zip Liberal, Kansas 67901
Contact Person Tammye J. Diseker
Phone (316) 624-8327

C S/2 NE SW Sec. 29 Twp. 32 S, Rg. 42W
1650 Ft. from South Line of Section
3300 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Company
City/State Wichita, Kansas
Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 1650 feet
County Morton
Lease Name SMITH Well 1-29
Ground surface elevation 3534 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 230'
Depth to bottom of usable water 400' 450'
Surface pipe by Alternate: 1x 2
Surface pipe planned to be set 1500'
Conductor pipe required
Projected Total Depth 5300 feet
Formation Chester & Marrow

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 4-29-87 Signature of Operator [Signature] Title Operations Secretary

For KCC User:
Conductor Pipe Required 100 feet Minimum Surface Pipe Required 100 feet per Alt.
This Authorization Expires 11-11-87 Approved By [Signature] 5-11-87

more on 6-4-87 398 1412"

MSW *[Signature]*

C S/2 NE SW Sec. 29 Twp. 32 S, Rg. 42W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>3600</u>	feet depth with	<u>40</u>	size of	<u>Class H Cement</u>
2nd plug @ <u>2850</u>	feet depth with	<u>40</u>	size of	"
3rd plug @ <u>1440</u>	feet depth with	<u>50</u>	size of	"
4th plug @ <u>800</u>	feet depth with	<u>20</u>	size of	"
5th plug @ <u>40</u>	feet depth with	<u>10-15</u>	size of	"
(2) Rathole with <u>15</u>	size	<u>D.G.</u>	(b) Mousehole with <u>10</u>	size

PUSHER Tom Hasket

TD 5400 FORMATION St Louis

SURFACE PIPE 8 7/8 @ 1411

ANHYDRITE 1599 ELEVATION

STARTING TIME & DATE 2 AM 6-19

COMPLETION TIME & DATE 1:15 AM

1st PLUG @ 3600 FT. W/ 40 SX

2nd PLUG @ 2850 FT. W/ 40 SX

3rd PLUG @ 1440 FT. W/ 50 SX

4th PLUG @ 1000 FT. W/ 20 SX

RAT HOLE CIRCULATED W/ 40-0 10 SX

MOUSE HOLE CIRCULATED W/ 10 SX

WATER WELL PLUGGED W/ 60/40 6 7/8 SX

CEMENT COMPANY Dravel

TECHNICIAN

RECEIVED
JUN 24 1987
CONSERVATION DIVISION
Wichita, Kansas

Blair Barlow was called by [Signature]