

1 020297

2-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-21,029-0000

C SE SW, SEC. 33, T 32 S, R 42 W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Arnold Well # B-1

Operator: Anadarko Petroleum Corporation
Name &

County Morton 170.11

Address P.O. Box 351

Well Total Depth 5234 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1351

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Never produced

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3 p.m. Day: 22 Month: 2 Year: 19 90

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5060' Perfs at 4816-18' squeezed off, 4793-98' PBD 4812'

1st plug pump 1 sx hulls and 20 sx cement at perfs, shoot pipe at 3000', load hole with mud,

2nd plug pump 55 sx cement at 1370',

3rd plug pump 50 sx cement at 750',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barloe
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30 p.m. Day: 24 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perforations,

shot pipe at 3000', loaded hole with mud,

2nd plug pumped 55 sx cement at 1370',

3rd plug pumped 50 sx cement at 750',

4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 3000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-2-90

INV. NO. 27582

2-24

2-27-90

Signed Glenn R. Barloe
(TECHNICIAN)