

To: 1 031040
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-18
API NUMBER 15-129-20,223-0000

TECHNICIAN'S PLUGGING REPORT
Operator License # 6593
Operator: Coastal Oil & Gas Corporation
Name & Address 221 North Robinson, Suite 1700
Oklahoma City, OK 73102

SE NE SE, SEC. 34, T 32 S, R. 42 W/E
1375 feet from S section line
150 feet from E section line
Lease Name Neuerberg Well # 2-34
County Morton 107.58
Well Total Depth 3310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 647

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Dowell License Number _____
Address Ulysses, KS

Company to plug at: Hour: 10 a.m. Day: 18 Month: 10 Year: 19 89

Plugging proposal received from Joe Lima
(company name) Coastal Oil & Gas Corporation (phone) 316-356-1276

were: 4 1/2" at 3289' PBTD 3249' Perfs at 2664-70, 3006-34, 3061-3119'
1st plug 100 sx cement down 4 1/2" casing,
2nd plug 100 sx cement down annulus.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5:45 P.m. Day: 18 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Casing parted at 1980' while drilling cement 1800'-2150'.
1st plug at 1980-0' with 113 sx 65/35 Pozmix,
2nd plug pumped down 8 5/8" with 113 sx 65/35 Pozmix and 65 sx common cement.

NOTE: THIS PLUGGING WITNESSED BY ED KNOBLOCH 10-24-89
OCT 24 1989

Remarks: Used 65/35 Pozmix and common cement by Dowell. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to be observed this plugging.)

DATE 10-30-89

Signed Steve Dumont
(TECHNICIAN)

INV. NO. 26364
10-18