

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21478-00-00
Spot: CNWNE Sec/Twnshp/Rge: 34-32S-42W
4390 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: RATZLAFF A Well Number: 1-34
County: MORTON Total Vertical Depth: 5328 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 73.16
Surface Casing: Size 8.625 feet: 1434 WITH 475 SX CMT
Production: Size 4.5 feet: 5328 WITH 200 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/30/2002 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4860' & 4 SX CMT. PLUG AT 1460' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 0-40' WITH 15 SX CMT. USE 15 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/30/2002 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 5258'. PERFS AT 4913-14'. SAND BACK TO 4860' WITH 4 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" TO 1450'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2" TO 500'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 4 1/2" TO 40'. PUMP 15 SX CMT TO SURFACE.

RECEIVED
JAN 10 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3041' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART
(TECHNICIAN)

INVOICED
DATE 1-18-03
INV. NO. 2003061067

FORM CP 2/3