

To: 1 100086 1-3
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-129-21,445-0000
NW SW, SEC. 31, T. 32 S, R. 41 W
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Milam A Well # 1
County Morton 123.46
Well Total Depth 3799 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 784

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 3 Month: 1 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 3367', TOCS 425' gauge, PBD 3325', Perfs at 3134-3259'
1st plug pump 2 sx hulls and 25 sx cement,
2nd plug pump 100 sx cement at 850-0'.
Check backside.

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 - 1 PM 12:51
6-7-97

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 3 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement from 3168-2968',
2nd plug displaced with mud to 850', pumped 90 sx cement from 850-0',
3rd plug pumped 5 sx cement down 8 5/8" X 5 1/2" annulus and pressured up to 500 psi.

Remarks: Used common cement by Sargent & Horton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOLVED
I ~~do not~~ do not approve this plugging.

DATE JAN 13 1997
WV. NO. 47341

Signed Gary Winters
(TECHNICIAN)