

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20567-00-01  
Spot: NWSE Sec/Twnshp/Rge: 34-32S-41W  
1980 feet from S Section Line, 2002 feet from E Section Line  
Lease/Unit Name: BERRYMAN RICHFIELD U Well Number: 9-3  
County: MORTON Total Vertical Depth: 5084 feet

Operator License No.: 32659  
Op Name: PHOENIX PETROCORP, INC.  
Address: 15700 CUSTER TRAIL  
FRISCO, TX 75035

Conductor Pipe: Size \_\_\_\_\_ feet: 8 1/2  
Surface Casing: Size 8.625 feet: 1383 WITH 800 SX CMT  
Production: Size 5.5 feet: 5084 WITH 250 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: EOR UIC Docket No: E18039.17 Date/Time to Plug: 10/07/2002 9:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4930' WITH 2 SX CMT. SHOOT OFF AT 1400'. PUMP 50 SX CMT ON BOTTOM. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/07/2002 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5044'. PERFS AT 4986-94'. SET CIBP @ 4930' WITH 2 SX CMT. 1ST PLUG LOAD HOLE WITH MUD. PUMP 50 SX CMT AT 1400'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 550'. LOAD HOLE AND PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH CASING TO 40' & PUMP 10 SX CMT TO SURFACE. LAST JOINT OF 5 1/2" OUT OF HOLE WAS FULL OF HOLES.

RECEIVED  
OCT 17 2002  
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 1423' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland (TECHNICIAN)

INVOICE OCT 09 2002

DATE 10-18-02

INV. NO. 2003060658

FORM CP 2/3